

ADD RIGHT WEIGH PLUMBING -
Truck (2 Port)

Supply & Fit Right Weigh Scales Bluetooth 2
PORT. Exterior mount digital gauge with
Bluetooth Operation.
201-EBT-02-B

Alternative Option:

Option 2: 4 port commonly used on Volvo
Suspension or UD with Volvo Suspension (at
additional charge)

****PLEASE NOTE IF INSTALLING HOIST BURST
VALVE ON TRAILER & WEIGHT GAUGES
COMBINED, THEN TRUCK WILL NEED X 2
TRIMATIC AND 1 X PBR COUPLING**

ADD RIGHT WEIGH SCALES - Truck
(4 Port)

Supply & Fit Right Weigh Scales Bluetooth 4
PORT. Exterior mount digital gauge with
Bluetooth Operation.
Commonly used on Volvo Suspension or UD with
Volvo Suspension as it has 4 airbags per axle)
201-EBT-04-B

****PLEASE NOTE IF INSTALLING HOIST BURST
VALVE ON TRAILER & WEIGHT GAUGES
COMBINED, THEN TRUCK WILL NEED X 2
TRIMATIC AND 1 X PBR COUPLING**

ADD RIGHT WEIGH SCALES - Dog (2 Port)

Supply & Fit Right Weigh Scales Bluetooth 2 PORT. Exterior mount digital gauge with Bluetooth Operation.
201-EBT-02-B

Alternative Option:

Option 2: 4 port commonly used on Volvo Suspension or UD with Volvo Suspension (at additional charge)

Please note that if Trailer has Burst Valve, Right Weigh Scales in dash to be plumbed on additional auxiliary connector at an additional cost e.g. Nitto fittings. If Bluetooth module, then trimatic is ok.

****PLEASE NOTE IF INSTALLING HOIST BURST VALVE ON TRAILER & WEIGHT GAUGES COMBINED, THEN TRUCK WILL NEED X 2 TRIMATIC AND 1 X PBR COUPLING**

ADD RIGHT WEIGH SCALES - Dog (plumbing only)

Plumbing only is the service required when your truck is already fitted with a Right Weigh In-Dash Screen (202-DDG-02). This means Trimatics need to be plumbed and fitted to both Truck and Trailer.

Please note that if Trailer has Burst Valve, Right Weigh Scales in dash to be plumbed on additional auxiliary connector at an additional cost e.g. Nitto fittings. If Bluetooth module, then trimatic is ok.

****PLEASE NOTE IF INSTALLING HOIST BURST VALVE ON TRAILER & WEIGHT GAUGES COMBINED, THEN TRUCK WILL NEED X 2 TRIMATIC AND 1 X PBR COUPLING**

ADD PBS (OD DRAWBAR)

If after calculations OD drawbar is required:

OD drawbar(Over Dimension) plate (if required) is usually expected to be issued 4 to 6 weeks after delivery of trailer or after registration number is available. It can be delayed further depending on NHVR workload. Technically, customer is not allowed to use the drawbar, until a modification plate is fixed.

* ADD \$1625 inc. OD Drawbar (section 87) including VASS certification. (may not be required on all builds subject to calculations)

ADD PBS CALCULATION (no certification)

This service is to calculate and build to PBS specifications. This price does not include any certificates but drawings and in-house build calculations will be supplied to you for approval from your own engineer.
